

MAGNUM 7 MATERIALS LIST

QTY	MATERIAL	DESCRIPTION	ALL	4' WIDE	5' WIDE		4' LONG	5' LONG	8' LONG	10' LONG
LOWER FRAME										
2	1.5 X 2 X 11 GA WALL RECT TUBE	1.5X2 TOP TUBES UNDER RAILS					72.00	84.00	120.00	144.00
2	3 X 3 X 14 GA TO 1/8 WALL SQ TUBE	3X3 TOP TUBES UNDER RAILS					72.00	84.00	120.00	144.00
4 to 8	3 X 3 X 14 GA TO 1/8 WALL SQ TUBE	3X3 CROSS SUPPORT TUBES		62.00	74.00		4 or 6	4 or 6	6 or 8	6 or 8
2	3 X 3 X 14 GA TO 1/8 WALL SQ TUBE	3X3 BOTTOM TUBES					48.00	60.00	96.00	120.00
4	3 X 3 X 14 GA TO 1/8 WALL SQ TUBE	3X3 LEGS	30.00							
0 or 2	3 X 3 X 14 GA TO 1/8 WALL SQ TUBE	3X3 CENTER UPRIGHT	15.00	OPTIONAL ON 4X4 OR 5X5, 2 REQUIRED ON 4X8 OR 5X10						
4	1/2 X 3 HOT ROLLED STEEL	FOOT	5.00							
4	1/4 X 3 HOT ROLLED STEEL	RAIL END STOPS	6.25							
WATERBED										
2	3 X 3 ANGLE ANY THICKNESS	SIDE ANGLES (MITER ENDS)					54.00	66.00	102.00	126.00
2	3 X 3 ANGLE ANY THICKNESS	END ANGLES (MITER ENDS)		54.00	66.00					
3	1 X 2 RECT TUBING ANY THICKNESS	SLAT SUPPORT TUBES					53.50	65.50	101.50	125.50
	1 X 1 X ANGLE ANY THICKNESS	SLAT SUPPORT ANGLES	2.81	QUANTITY REQUIRED			53	65	101	125
1	16 GA OR HEAVIER STEEL SHEET	WATERBED BOTTOM	DIMS	48.00	60.00		48.00	60.00	96.00	120.00
CABLE TRACK SUPPORT										
1	C4 X 4.5 LB/FT STEEL CHANNEL	SUPPORT CHANNEL					72.00	84.00	67.50	79.50
SIDE RAILS										
2	1/2 X 3 COLD ROLLED STEEL	SIDE RAILS					72.00	84.00	120.00	144.00
SLATS										
			NOMINAL - MEASURE BED				QUANTITY REQUIRED			
	1/8 X 2 HOT ROLLED STEEL	SLATS (MEASURE BED)		53.50	65.50		17	21	33	41
GANTRY										
1	3 X 3 X 14 GA TO 1/8 WALL SQ TUBE	GANTRY MAIN TUBE		70.50	82.50					
1	1 X 3 X 16 GA TO 1/8 RECT TUBE	CABLE TRACK SUPPORT		61.50	73.50					